

Europäisches Patentamt

European Pat nt Office

Offic europé n des brevets



(11) EP 0698510 A2

(12)

#### **EUROPEAN PATENT APPLICATION**

(43) Date of publication: 28.02.1996 Bulletin 1996/09

(51) Int Cl.6: **B60C 9/22**, B60C 9/20

(21) Application number: 95305805.4

(22) Date of filing: 21.08.1995 .

(84) Designated Contracting States:

DE FR GB IT

(30) Priority: 23.08.1994 DE 4429899 23.02.1995 DE 19506381 17.03.1995 DE 19509824

(71) Applicant: SP REIFENWERKE GMBH D-63450 Hanau (DE)

(72) Inventors:

Damke, Roland
 D-73579 Freigericht-Somborn (DE)

Gerresheim, Manfred
 D-73179 Obertshausen-Hausen (DE)

Nau, Robert
 D-63456 Hammersbach (DE)


Winter, Hans-Joachim
 D-63571 Gelnhausen (DE)

Lowenhaupt, Bernd
 D-64625 Bensheim (DE)

(74) Representative: Stewart, Charles Geoffrey Fort Dunlop, Erdington, Birmingham B24 9QT (GB)

# (54) Pneumatic vehicle tyre

(57) A pneumatic vehicle tyre comprises a single ply or multi-ply radial carcass anchored to bead rings, a tread, and a breaker arrangement provided between the carcass and the tread. The breaker arrangement is preferably built up of at least two cut breaker plies with the threads or cords of the cut breaker plies, which serve as strength carriers and extend parallel to one another in the respective layer, crossing at a predeterminable angle to the central mid-circumferential plane. The tyre also comprises at least one cover ply of cords of threads extending at least substantially in the circumferential direction of the tyre and surround the breaker arrangement at least in its edge regions. To reduce the tyre weight while simultaneously ensuring good tyre characteristics the breaker arrangement (4) has threads or cords (9) of non-metallic material and a material with a low thermal shrinkage or no thermal shrinkage is used as the material for the threads or cords (8) of the cover ply (5). An extension of the tyre is ensured into the tyre mould during its manufacture through the choice of the material of the threads of cords of the cover ply (5) alone, or in conjunction with the nature of the construction and/or of the application of the cover ply (5) and/or through the nature of the construction of the threads or cords (8) of the cover ply (5), but an extension of the tyre which goes beyond this is simultaneously counteracted.



35

#### Descripti n

The invention relates to a pneumatic vehicle tyre comprising a single ply or multi-ply radial carcass anchored to bead rings, a tread, a breaker arrangement provided between the carcass and the tread, the breaker arrangement preferably being built up of at least two cut breaker plies with the threads or cords of the breaker plies, which serve as strength carriers and extend parallel to one another in the respective layer, crossing at a predeterminable angle to the mid-circumferential plane and also comprising at least one cover ply of cords of threads extending at least substantially in the circumferential direction of the tyre and surrounding the breaker arrangement at least in its edge regions.

Whereas the radial carcass forms the support construction of the tyre and gives strength to the tyre, the breaker arrangement provided between the carcass and the tread, which consists of at least two cut breaker plies, serves to give the pneumatic vehicle tyre the desired driving characteristics, in particular the necessary stability. In order to prevent separation of the breaker arrangement, in particular at high speeds, this separation predominantly occurring in the edge regions of the breaker lies, the breaker arrangement is, at least in this region, covered over with a cover or bandage layer having threads or cords which extend at least substantially in the circumferential direction of the tyre.

Pneumatic vehicle tyres of the named kind are customarily manufactured using a cylindrical drum by laying the individual tyre components, such as the carcass and sidewalls, one after the other onto the drum. After the bead rings have been set in place and the carcass tumed over around the, the tyre blank is then shaped to a toroid, the breaker plies applied to the tread and then the assembly is placed in a tyre mould in which the tyre profile is formed and the tyre is vulcanised.

In order to finally shape the tyre blank into the tyre mould, the individual components of the tyre must be extensible in order to allow the final stretch of the tyre into the tyre mould.

On the other hand, an extension of the tyre under static or dynamic loading should be avoided as far as possible in the finished tyre. While the breaker plies permit an extension to the requisite degree as a result of their cords which are arranged in a crossed arrangement at a predeterminable angle to the mid-circumferential plane, this can only be achieved for the cover or bandage ply, with its cords which extend substantially in the circumferential direction of the tyre, through a suitable choice of the cord material. However, in this respect account should additionally be taken of the fact that the cov-

r or bandage ply serves to prevent a separation of the breaker arrangement. Despite the extensibility required for the formation of the tyre, the cover or bandage ply must therefore have adequate strength.

Nowadays, breaker plies customarily contain steel cords as reinforcing elements, whereas the cover ply

comprises nylon cords. However, the use of ste I cords in the breaker arrangement is disadvantageous having regard to the increasing endeavour to reduce tyre w ight.

The invention is thus based on the object of further development a pneumatic vehicle tyre of the initially named kind so that its weight is reduced as much as possible without impairing the required characteristics of the pneumatic vehicle tyre.

This object is satisfied in that the threads or cords of the breaker arrangement are threads or cords of non-metallic material; in that a material with low thermal shrinkage or no thermal shrinkage is used as the material for the threads or cords of the cover ply; and in extension of the tyre is ensured into the tyre mould during its manufacture, through the choice of the material of the threads or cords of the cover ply alone, or in conjunction with the nature of the build-up and/or of the application of the cover ply and/or through the nature of the build-up of the threads or cords of the cover ply, but with an extension of the tyre which goes beyond this being simultaneously counteracted.

As a result of the use of non-metallic reinforcing elements instead of steel in the breaker arrangement, the tyre weight is advantageously reduced. In order to nevertheless give the tyre the desired properties, the cover ply is formed in the given manner.

The choice is thus made so that the extension of the green tyre necessary for moulding the green tyre into the tyre mould is possible; so that no shrinkage of the tyre occurs on heating up of the completed tyre after vulcanisation, or during use; and so that extension of the tyre under static load (air pressure) or dynamic load (centrifugal force) is counteracted with a force which is as large as possible in order to prevent an undesired growth of the tyre.

In contrast to a pure steel radial tyre, there is the problem, when non-metallic reinforcing elements are used in the breaker arrangement, that the breaker material has no or only a small bulk modulus. A shrinkage of the cover ply as a result of warming would therefore lead to a deformation of the tyre and thus to a worsening of the tyre properties up to its destruction.

In accordance with the invention, a material for the threads of cords of the cover ply is preferred which has a modulus of elasticity which is as large as possible, at least in the initial range of tyre extension, but which still just permits an extension of the tyre into the mould during manufacture. An undesired extension of the tyre during use is thereby substantially prevented.

Rayon has proved to be a particularly suitable material for the thread or cords of the cover plies. Rayon has a comparably high initial modulus, particularly in comparison to nylon, i.e. a relatively steep gradient of the stress-strain curve (forc -extension curve) which is large enough to counteract an undesired extension of the tyre but which permits an extension of the tyre into the tyre mould. Moreover, rayon is practically free of thermal

50

25

35

45

50

*5*5

shrinkage.

Polyester may also be used for the threads or cords of the cover ply providing that its modulus of lasticity is sufficiently large and its thermal shrinkage sufficiently small. High-modulus-low-shrinkage polyesters (HMLS) of this kind are already tested.

Furthermore, threads or cords or aramid, or of a hybrid material with aramid, have proved to be advantageous for the cover ply. Aramid and the name hybrid materials are characterised by a particularly high tensile strength and thus prevent undesired tyre growth under static or dynamic loading. In this way, the tyre of the invention has particularly good fast running characteristics

The extension of the tyre necessary for the forming of the tyre tread or profile can be set via the build-up of the cover ply, in particular via the titre, i.e. the weight related to a specific length, of the threads or cords and their density in the respective ply, via the degree of twist of the cords and via the type of winding of the cover ply. Thus, the extensibility of the tyre increases with reducing thread density and reducing titre. In the same way the extensibility of the cords can be increased by a higher twist. Finally, the winding density and strength of the cover ply also co-determine the extensibility of the tyre.

It has surprisingly turned out that when using these measures, even when using high modulus materials, in particular aramid materials, no problems arise during forming of the tyre profile.

In any case, the threads or cords of the cover ply are preferably selected to be as thin as possible and as thick as necessary. The weight of the cover ply and thus the tyre weight can be reduced in this way.

In a further embodiment of the invention, the breaker arrangement contains cords or threads of textile material, in particular or aramid. Aramid has a particularly high strength combined with a low weight. In comparison to steel, the weight can be significantly reduced. Particularly good tyre properties are achieved by the combination of an aramid breaker and a rayon cover ply. In place of aramid, glass fibres or carbon fibres can also be used in the breaker arrangement.

In place of aramid, rayon or HMLS polyester can be used for the reinforcement elements of the breaker arrangement. Good tyre properties also result from this approach.

In accordance with a further embodiment of the invention, the geometrical arrangement of the cover ply and/or the thread or cord density in the cover ply are used in addition to the selection of the cord or thread material of the cover ply for achieving the desired extension behaviour of the tyre.

For example, the cover ply can be provided only in the edge regions of the breaker arrangement where the dang r of separation of the breaker arrangement is the highest. Through this arrangement of the cover ply, the xtension of the tyre into the tyre mould in the central axial region is practically unimpaired by the cover ply.

With a cover ply which surround the breaker arrangement over its ntire width, the threads or cords of the cover ply in the shoulder region of the tyr can consist of a material which is essentially non- xtensibl. In the middle tyre region disposed between the two shoulder regions the threads or cords of the cover ply can consist of a material which permits an extension of the tyre by a predeterminable amount under the conditions which prevail during tyre manufacture, but can oppose an extension of the tyre which goes beyond this with the largest possible resistance.

Through this differential choice of material for the threads or cords of the cover ply in the shoulder region. on the one hand, and in the central tyre region, on the other hand, the extension of the tyre which is necessary for the arching of the tyre blank and for the formation of the tyre is made possible and the shoulder regions which are particularly endangered by separation effects ar strengthened. The use of an essentially inextensible cord material in the shoulder regions is possible because the tyre extension which required here is very low. In th central tyre region where a considerable tyre extension is necessary a larger extension is made possible by a suitable choice of material. Through adjustment of the permissible extension to the degree required during tyre manufacture an extension of the finished tyre beyond this dimension can be largely prevented.

Aramid has turned out to be a particularly suitable material for the threads and cords in the shoulder region of the cover ply and rayon for the threads or cords of the cover ply in the central region of the tyre. Whereas aramid has only a very low extensibility, rayon permits an extension up to a certain degree but generates a large restraining force for an extension which goes beyond this. The finished tyre thereby becomes particularly stable.

The cover ply can be formed in the shoulder regions of the tyre and/or in the central region of the tyre by a helically wound strip bandage, a so-called jointless band (JLB). The cover ply in the central region of the tyre can also be formed as a broad band in accordance with one embodiment of the invention.

The sections of the cover ply in the shoulder regions and in the central tyre region can be respectively arranged either abutting one another or overlapping one another. When using a strip bandage for both the two shoulder regions and also for the central tyre region, the single strips of different material can also be directly wound adjoining one another around the tyre, that is to say the start of the strip which is wound around the centr of the tyre is set at the end of the strip wound around the one shoulder region and the start of the strip wound around the strip wound around the centre of the tyre. In this manner, a particular uniform cover ply is obtained and the tyre characteristics are improved.

The permissible extension of the cov r pty during the manufacture of the tyre can be restricted by choice of the

cord material in the shoulder region to a maximum of ca. 0.1 to 0.5%, in particular to circa 0.3%, whereas in the central region of the tyre a p missible extension during manufacture, for example in the range between 2 to 3%, in particular 2.5 to 2.7%, can be set through the choice of the cord material. With this choice, particularly good tyre characteristics can be obtained.

These extension relationships can be particularly advantageously set through the combination of aramid in the shoulder regions of the tyre, and rayon in the central tyre region as materials for the cords of the cover ply. The force-extension curves of aramid and rayon have a favourable relationship relative to each other for this purpose. That is to say, substantially the same sized forces are required in the shoulder region and in the central region of the tyre for the extension of the breaker with the cover ply during the moulding of the tyre with this choice of material, whereby a uniform moulding and harmonious tyre characteristics are achieved.

Aramid is preferably used as a material for the threads or cords of the breaker arrangement with this layout of the invention. In this way, the tyre weight is kept low. In conjunction with rayon for the threads or cords of the cover ply in the central region of the tyre and aramid in the two shoulder regions of the tyre, one obtains a particularly advantageous tyre assembly with high strength and low weight. Through the use of rayon which has no thermal shrinkage it is ensured that during heating of the tyre no deformations arise as a result of the lacking bulk modulus of textile cut breaker plies. The combination of aramid in the shoulder region and rayon in the central region of the tyre could however basically also be used with steel breakers. The tyre weight would however then be higher.

The extension behaviour of the cover ply, i.e. the modulus of elasticity of the cover ply as a whole, can be directly influenced by the thread or cord density. A high cord or thread density produces a high modulus of elasticity and, correspondingly, a small modulus of elasticity of the cover ply is produced by a small thread or cord density.

A further possibility for influencing the extension behaviour of the cover ply through its construction is to alter the winding density and/or the winding strength in order to adjust the extension behaviour of the cover ply, i.e. its modulus of elasticity, in a deliberate manner. A large modulus of elasticity of the cover ply can thus be set by a high winding density and/or by a high winding strength whereas, correspondingly, a small modulus of elasticity can be set by a small winding density and/or winding strength.

In accordance with a further embodiment of the invention, the winding density and/or winding strength are selected differently across the width of the tyre, with them being preferably selected to be respectively higher or larger in the edge regions of the breaker arrangement. This allows the desired extension behaviour, and, in genral, the desired properties of the tyre to be taken into

account particularly well.

As already described, a high modulus of elasticity is necessary in the edge regions of the breaker plies, which correspond to the shoulder regions of the tyre, in order to counteract the particularly large danger of separation of the breaker plies here, whereas in the central axial region of the tyre a smaller modulus of elasticity of the cover ply is sufficient.

In accordance with a further embodiment of the invention, the setting of the desired extension properties of the cover ply can be achieved via the build-up of the cords or threads of the cover ply by a corresponding selection of the degree of twist of these threads or cords. The cords or threads are given an additional elasticity by increasing their degree of twist in the cover ply thus leading to a reduction of the modulus of elasticity of the cover ply. On the other hand, a larger modulus of elasticity can be produced by a reduced degree of twist.

In order to set the desired extension behaviour further, measures have proved to be particularly suitable. Thus, the cover ply can cover over the entire breaker ply or only a part of it, in particular the two edge regions of the breaker plies. In the first case in particular, the cover ply can also be constructed as a singly-folded twin-ply.

In a cover ply made of helically wound strips, a so-called JLB (jointless band), the individual strip windings can overlap one another and the width of overlap can be selected to be different over the width of the tyre. In this manner the extension properties can also be varied in a controlled manner over the width of the tyre. In particular, a large modulus of elasticity of the cover ply can be provided in the shoulder regions of the tyre, whereas a small modulus of elasticity can be provided in the central axial region of the tyre. This can, for example, be achieved by providing an overlap of the strip windings only in the regions which cover over the two edge regions of the breaker arrangement, or by making this overlap particularly large here.

The winding sense and winding direction of the strip bandage can, in accordance with the further embodiments of the invention, also be different over the width of the tyre. In particular, the winding sense and winding direction on one side of the mid-circumferential plane can be opposite to that on the other side of the mid-circumferential plane. This also allows the tyre properties to be influenced in a controlled manner.

In summary, the modulus of elasticity of the cover ply can be adjusted in a controlled manner by using the various measures described above, that is to say, the stress-strain curve (force extension) of the cover ply can be given a desired characteristic.

Moreover, the breaker arrangement can also be designed in different ways. In particular one or more of the breaker plies can have a multi-part construction, for instance with a gap in the central axial region. The type and construction of the reinforcing elements of the breaker arrangement can also be used to influence the extension properties of the tyr in a similar mann r as for the

30

cover ply.

Furthermore, the breaker arrangement can consist, in accordance with the invintion, either exclusively of non-metallic briaker plies or can consist of both non-mitallic and steel breaker plies (so-called hybrid construction). In both cases the cover ply design in accordance with the invention has a favourable effect on the tyre properties.

In accordance with a further layout of the invention, cords or threads of the same material and with the same titre are used in the breaker plies and in the cover ply. Through this layout, the storage of materials is made easier and more cost-favourable since only one particular cord need be kept available for each type of tyre.

Cords consisting of two twisted aramid threads with a titre of respectively 1670 dtex., i.e. grams per 10,000 metres, and also a cord density in the breaker plies of ca. 70 to 120 cords per 10 centimetres and in the cover ply of ca. 60 to 90 cords per 10 centimetres have proved to be particularly suitable, with the breaker arrangement preferably being built-up of two aramid breaker plies and one aramid strip bandage serving as the cover ply.

In accordance with a further embodiment of the invention, the cord density in the breaker plies and in the strips of the cover ply are of the same size. This layout has the advantage that the breaker plies and the strips for the cover ply can be manufactured from a single rubberised ply. A rubberised ply can thus also be manufactured with the desired cords at the required cord density in the form of an endless band from which then both the breaker plies and also the strips for the cover ply can be cut off. In this way, the manufacturing of the tyre of the invention is simplified.

A particularly favourable method for the manufacturing of such a pneumatic vehicle tyre lies in first manufacturing a rubberised ply with textile cords at the required cord density and in that the strips required for the cover ply are cut-away from this ply at the side margins, whereas the remaining part of the rubberised ply is used for the breaker plies. In this way, a rubberised ply can be manufactured as a continuous band from which then both the strips for the cover ply and also the breaker plies can be cut off. The manufacture is thereby made particularly simple and practically no cutting losses arise.

Embodiments of the invention are shown in the Figures and are described in the following.

They show:

Figure 1 a cross-section through a pneumatic vehicle tyre in accordance with the invention;

Figure 2 a perspective partial view of a sectioned tyre in accordance with the invention;

Figures 3 to 34 various variants of the cover ply in 55 accordance with the invintion shown schematically;

Figure 35 a strain or extension diagram of tyres with

t xtile br aker plies and with various cover plies in comparison;

Figure 36 a perspective illustration of a rubberised ply for us in the tyre in accordanc with Figure 1;

Figure 37 a schematic illustration of a first variant of a breaker and cover ply arrangement in accordance with the invention to a scale reduced relative to Figure 1; and

Figure 38 a further variant of a breaker and cover ply arrangement in accordance with the invention in an illustration corresponding to Figure 37.

The tyre shown in Figure 1 has a radial carcass 2 anchored to the bead rings 1, a tread 3 and a breaker arrangement 4 comprising two breaker plies positioned between the carcass 2 and the tread 3, as well as a cover ply 5 surrounding the breaker arrangement. The bead rings 1 are each provided with a bead core 6 on which a bead filler or bead apex 7 is arranged.

It can be seen from Figure 2 that both the break r plies of the breaker arrangement 4 and also the cov r ply 5 comprise mutually parallel cords or threads 8 and 9 respectively in the respective ply. Whereas the cords or threads 8 of the cover ply 5 extend substantially in the circumferential direction of the tyre, the cords or threads 9 of the two breaker plies 4 of the breaker arrangement cross each other at a particular angle relative to the central circumferential plane of the tyre.

Figures 3 and 4 show the arrangement of the cover ply 5 radially outside the breaker arrangement 4. In Figure 3 the cover ply 5 surrounds the breaker arrangement 4 over its entire width, whereas in Figure 4 only the edge regions of the breaker arrangement 4 are surrounded by the cover ply 5 which is now a two-piece cover ply.

In Figures 5 and 6, the cover ply 5 is, in contrast to Figures 3 and 4, formed as a helically wound strip bandage (JLB), with the winding of the strip bandage 13 taking place from left to right in Figure 5 and from right to left in Figure 6 as is indicated in Figures 5b and 6b by the bandage part piece 10 by the arrows 11 and 12 respectively.

In Figures 7 and 8 an embodiment is shown in which the individual windings of the strip bandage 13 overlap, with the winding direction corresponding on the one hand to that of Figure 5 and on the other h and to that of Figure 6.

In the Figures 9 and 10, the winding direction on the left and the right of the central circumferential plane 14 is in each case different. Otherwise, these embodiments correspond to those of Figures 7 and 8.

In Figures 11 to 16, the overlap between the individual windings of the bandage strip 13 is different over the width of the tyre. In Figures 11 to 14 an overlap only occurs in the edge regions of the breaker arrangement 4 and the strip bandage 13 is wound in the central axial region in abutting form or with gaps. In contrast, in Fig-

1.1

ures 15 and 16 an overlap occurs over the entire width of the tyre, this overlap being larger in the edge regions of the breaker arrangement 4 than in the c ntral axial regior of the tyre. The winding direction is in each case different as is indicated with the arrows 11 and 12 respectively.

In Figures 17 to 28, the cover ply 5 is only provided in the edge regions of the breaker arrangement 4. In Figures 17 to 20 each of the individual turns overlap and the winding direction is that indicated by the arrows 11 and 12. In contrast, Figures 21 to 24, the individual turns of the strip bandage strip do not overlap. The winding direction is also shown here by the arrows 11 and 12. Figures 25 to 28 correspond as regards the overlap and the winding direction to figures 17 to 20, but in comparison to these Figures have an opposite winding sense.

In Figures 29 to 32, the cover ply 5 is formed as a twin ply and is folded once wither in the left or in the right edge region of the breaker ply 4. Although in Figures 29m and 30 the cover ply 5 is formed as a broad band, the cover ply 5 shown in Figures 31 and 32 is formed as a helically wound strip bandage 13.

Figures 33 and 34 show a cover ply 5 which in each case covers over a breaker arrangement 4 with differently formed breaker plies. In Figure 33 the radially outer breaker ply is formed in two parts with a gap lying in the central axial region of the tyre. In contrast, in Figure 34, it is the radially inner breaker ply which is formed in two parts and has such a gap.

The diagram of Figure 35 shows the effect which can be achieved with a cover ply 5 in accordance with the invention. The change of the tyre diameter of a pneumatic vehicle tyre with textile breaker plies is shown and indeed, firstly, for a tyre in accordance with the invention with a strip bandage with rayon cords (curve I) and secondly for a tyre with a strip bandage of nylon cords (curve II). The tyre diameter is shown at various stages of the tyre manufacture as well as for the completed tyre at room temperature and when pumped up. The tyre diameter is given here as a percentage of the diameter of the green tyre.

One can see that with a tyre in accordance with the invention with a rayon cover ply (curve I) the tyre diameter remains almost unchanged throughout tyre production. On pumping the tyre up, its circumference increases by a small amount.

For a tyre with a nylon cover ply (curve II) the tyre diameter reduces by a considerably amount during vulcanisation due to the thermal shrinkage of the nylon. The tyre first reaches approximately the diameter of the tyre with a rayon cover ply when pumped up.

The strip bandage 13 can be cut off from a rubberised ply 15 from which the cut breaker plies of the breaker arrangement 4 are also manufactured. A rubberised ply 15 of this kind is shown in Figur 36. The rubberis d ply 15 has cords 16 which extend parallel to one another and which are formed in the illustrated exampl of two or thre threads 17 which are twisted togeth r. The cords 16 are enveloped with a caoutchouc mixture which was selected in accordanc with the desir d characteristics of the rubberised ply. The rubberised ply 15 however normally contains only cords 16 of two threads 17 or only cords 16 of three thr ads 17. Figure 36 thus only serves to illustrate various possibilities.

The cords 16 of the rubberised ply 15 can for example consist of two aramid threads which are twisted together and the titre of which amounts to 1670 dtex. The cord density in the rubberised layer 15 can preferably amount to between 70 and 120 cords per 10 centimetres.

The strips for the strip bandage 13 can be cut off from the marginal regions of the rubberised layer 15. The remaining part of the rubberised layer 15 is then used for the cut breaker plies of the breaker arrangement 4, with the remaining part of the rubberised ply 15 being cut for this purpose into individual cut breaker plies at an angle which corresponds to the desired cord angle of the respective cut breaker ply relative to the mid-circumferential plane 14.

A further possible layout of the cover ply 5 is shown in Figure 37. Here the cover ply 5 is formed in each of the two shoulder regions 18 by a respective helically wound strip bandage 19 and 20 respectively, and in the central tyre region 21 lying between them by a broad band 22. The two strip bandages 19 and 20 preferably have threads or cords of aramid, while the broad band 22 is provided with threads or cords of rayon.

The individual windings of the strip bandage 19 and 20 can also be arranged abutting one another or overlapping one another, other than in the schematic illustration of Figure 37. In just the same way, the two strip bandages 19 and 20 can be respectively arranged abutting the broad band 22 or can overlap the latter, with the strip bandages 19 and 20 or the broad band 22 being arranged radially outwardly as desired.

In the variant illustrated in Figure 38 a strip bandage 23 is also provided as the cover ply 5 in the central region 21 of the tyre, in addition to the two strip bandages 19 and 20 in the two shoulder regions 18 of the tyre. With this layout, the individual turns of the strip bandages 19 and 20 can be wound abutting or overlapping one another in a manner different from that illustrated. In just the same way, the individual turns of the strip bandage 23 present in the central region of the region 21 of the tyre can be arranged abutting or overlapping one another in a different manner from that illustrated.

The turns of the strip bandage 19 or 20 adjacent to the strip bandage 23 can respectively overlap the adjacent turns of the strip bandage 23 or can be overlapped by the latter or be wound abutting the latter. It is, however, also possible to place the start of the strip bandage 23 directly at the confronting end of the strip bandage 19 and to place the start of the strip bandage 20 directly at the end of the strip bandage 23. In this manner, a particularly uniform cover ply 5 aris s.

The threads or cords of the strip bandag s 19 and 20 also preferably consist of aramid in this variant,

25

35

40

45

50

55

whereas the threads or cords of the strip bandage 23 are again preferably formed of rayon. A break r arrangement 4 has in both variants preferably thr ads or cords or aramid. In this way, a particularly light and strong break r arrang ment is achieved.

The cover ply 5 is preferably so designed that under the condition which exists during tyre manufacture, in particular with the usual pressure during shaping of approximately 20 bar, a maximum extension of ca. 0.1 to 0.5%, in particular 0.3£ is possible in the two shoulder regions 18 of the tyre, whereas in the central tyre region 21 a possible extension is set in the range from 2 to 3%, in particular 2.5 to 2.7%. Through this choice, it is possible to ensure the extension required for the shaping into the tyre mould of the tyre blank built up on the cylindrical building drum in the middle tyre region 21, whereas in the shoulder regions 18, where practically no extension is necessary, a particularly firm covering over of the breaker arrangement 4 is achieved. In the mid-region 21 of the tyre this choice moreover counteracts further extension so that in the finished tyre a good strength of the breaker arrangement 4 is also given in the central region 21 of the tyre.

The regions of the cover ply 5 with aramid threads or cords can in all embodiments cover over the breaker arrangement 4 from approximately 10% up to approximately 35 to 40%. The central region of the tyre accordingly extends ca. 60 to 90% of the breaker arrangement 4.

The invention therefore allow a light tyre to be manufactured in an inexpensive manner which fulfils all the requirements for a modern tyre.

Further variations of the construction of the cover ply 5, of the arrangement of the cover ply 5 on the breaker ply 4 as well as of the materials used is of course possible within the scope of the invention. What always matters is to adjust the stress-strain (force-extension) curve of the cover ply 5 by varying the parameters indicated so that the desired extension behaviour of the tyre is achieved, i.e. one which, on the one hand, allows the tyre to be manufactured in a satisfactory manner with a clean formation of the tyre profile and, on the other hand, results in optimum tyre properties.

### Claims

1. A pneumatic vehicle tyre comprising a single ply or multi-ply radial carcass anchored to bead rings, a tread, a breaker arrangement provided between the carcass and the tread, the breaker arrangement preferably being built up of at least two cut breaker plies with the threads or cords of the cut breaker plies, which serve as strength carries and extend parallel to one another in the respective layer, crossing at a predeterminabl angle to the central mid-circumferential plane, and also comprising at least one cover ply of cords or threads extending at least substantially in the circumf rential dir ction of the tyr and surrounding the br aker arrang ment at least in its edg r gions, charact rised in that the breaker arrangement (4) has threads or cords (9) of non-metallic material; in that a material with a low thermal shrinkage or no thermal shrinkage is used as the material for the threads or cords (8) of the cover ply (5); and in that extension of the tyre into the tyre mould during its manufacture is ensured through the choice of the material of the threads or cords of the cover ply (5) alone, or in conjunction with the nature of the construction and/or of the application of the cover ply (5) and/or through the nature of the construction of the threads or cords (8) of the cover ply (5), but extension of the tyre which goes beyond this being simultaneously counteracted.

- A pneumatic vehicle tyre in accordance with claim

   characterised in that a material with the largest possible initial modulus of elasticity is used as the material for the threads or cords (8) of the cover ply (5) and only just permits an extension of the tyre into the tyre mould during manufacture.
  - 3. A pneumatic vehicle tyre in accordance with claim 1 or claim 2, characterised in that the cover ply (5) has threads or cords (8) of rayon, or of a polyester with a high modulus of elasticity and low thermal shrinkage, so-called HMLS polyester, or of aramid or of a hybrid material with aramid.
  - 4. A pneumatic vehicle tyre in accordance with one of the preceding claims, characterised in that the degree of twisting of the threads or cords (8) of the cover ply (5) and/or the geometrical arrangement of the cover ply (5) and/or the thread density or cord density in the cover ply (5) and/or the winding density and/or winding strength of the cover ply (5) and/or the nature of the construction of the breaker arrangement (4), in particular the nature of the construction of the threads or cords (9) of the breaker arrangement (4) are at least also used to set the desired extension behaviour.
  - 5. A pneumatic vehicle tyre in accordance with one of the preceding claims, characterised in that the winding density and/or winding strength of the cover layer (5) are selected to be different in the axial direction of the tyre and are in particular respectively higher or greater in the edge regions of the break r arrangement (4).
  - 6. A pneumatic vehicle tyre in accordance with one of the preceding claims, characterised in that the cover ply (5) is formed as a broad band which can also be formed by simple folding as a double ply.

- 7. A pneumatic vehicle tyre in accordance with one of the claims 1 to 5, characterised in that the cover ply (5) is formed as a helically wound strip bandage, with adjacent windings of the strip bandage (13) preferably overlapping at least in part, and indeed in particular only in the two regions of the cover ply (5) which cover over the two edge regions of the breaker arrangement (4), and with the width of overlap being selectable to differ over the width of the tyre.
- 8. A pneumatic vehicle tyre in accordance with claim 7, characterised in that the sense of winding and/or the winding direction of the strip bandage (13) are different in the axial direction of the tyre, and are in particular respectively opposite on one side of the mid-circumferential plane (I) to that on the other side of the mid-circumferential plane (I).
- 9. A pneumatic vehicle tyre in accordance with one of the preceding claims characterised in that no cover is present in the axially central region of the tyre and in particular only the two edge regions of the breaker arrangement (4) are covered over.
- 10. A pneumatic vehicle tyre in accordance with one of the claims 1 to 8, characterised in that the cover ply (5) surrounds the breaker arrangement (4) over its entire width, with the threads or cords of the cover ply (5) in the two shoulder regions (18) of the tyre preferably consisting of a material which is essentially non-extensible, preferably aramid, and consisting in the central tyre region (21) disposed between the two shoulder regions (18) of a material, preferably rayon, which permits an extension of the tyre by a predeterminable amount under the conditions which are present during tyre manufacture, but oppose an extension of the tyre which goes beyond this with a resistance which is as large as possible.
- 11. A pneunatic vehicle tyre in accordance with claim 10, characterised in that a helically wound strip bandage (19,20 and 23) serves as the cover ply (5) in the shoulder regions (18) and in the central tyre region (21).
- 12. A pneumatic vehicle tyre in accordance with claim 10, characterised in that the cover ply (5) is formed as a helically wound strip bandage (19,20) in the shoulder regions and as a broad band (22) in the central tyre region (21).
- 13. A pneumatic vehicle tyre in accordance with one of the preceding claims, characterised in that the cover ply (5) in the two shoulder regions (18) of the tyre is respectively arranged abutting the cover layer (5) in the central r gion (21) of the tyre, or overlapping the latter.

- 14. A pneumatic vehicle tyre in accordance with one of the prec ding claims, charact rised in that the cover ply (5) in the shoulder region (18) has an extensibility of at most ca. 0.1 to 0.5%, in particular ca. 0.3% and an extensibility in the central region (21) of the tyre in the range from 2 to 3%, in particular ca. 2.5 to 2.7%.
- 15. A pneumatic vehicle tyre in accordance with any one of the preceding claims, characterised in that the breaker arrangement (4) has threads or cords (9) of textile material, in particular of aramid or rayon or of HMLS polyester, or of glass fibre or of carbon fibr.
- 15 16. A pneumatic vehicle tyre in accordance with one of the preceding claims, characterised in that threads or cords (16) of the same material and with the same titre, i.e. weight related to a particular length, are used for the breaker arrangement (4) and for the cover ply (5), with the cord density preferably being the same in the individual breaker plies of the breaker arrangement (4) and in the cover ply (5).
- 17. A method of manufacturing a pneumatic vehicle tyre in accordance with claim 15, characterised in that the breaker arrangement (4) has two aramid breaker plies and in that an aramid strip bandage is provided as the cover ply (5).
  - 18. A pneumatic vehicle tyre in accordance with claim 16 or 17, characterised in that cords (16) of two twisted together aramid threads (17), each having a titre of 1670 dtex, i.e. grams per 10,000 metre, are used for the breaker arrangement (4) and the cover ply (5), in that the cord densities in the individual breaker plies of the breaker arrangement (4) amount to approximately 70 to 120 cords per 10cm, and in that the cord density in the cover ply (5) amounts to approximately 60 to 90 cords per 10cm.
  - 19. A method of manufacture of a pneumatic vehicle tyre in accordance with claim 16, characterised in that initially a rubberised ply (15) comprising textile cords (16) is manufactured with the desired cord density, and in that the strips required for the cover ply (5) are cut off from the edge of the rubberised ply (15), whereas the remaining part of the rubberised ply (15) is used for the individual plies of the breaker arrangement (4).

8

45

50









Fig. 2























Fig. 11




Fig. 12




Fig. 13




Fig. 14









Fig. 15



















## EP 0 698 510 A2










































Fig. 36









Europäisches Pat ntamt

European Pat nt Offi e

Offi européen des brevets



(11) EP 0 698 510 A3

(12)

# **EUROPEAN PATENT APPLICATION**

(88) Date of publication A3: 10.04.1996 Bulletin 1996/15

(51) Int Cl.6: **B60C 9/22**, B60C 9/20

(43) Date of publication A2: 28.02.1996 Bulletin 1996/09

(21) Application number: 95305805.4

(22) Date of filing: 21.08.1995

(84) Designated Contracting States: **DE FR GB IT** 

(30) Priority: 23.08.1994 DE 4429899 23.02.1995 DE 19506381 17.03.1995 DE 19509824

(71) Applicant: SP REIFENWERKE GMBH D-63,450 Hanau (DE)


(72) Inventors:

Damke, Roland
 D-73579 Freigericht-Somborn (DE)

- Gerresheim, Manfred
   D-73179 Obertshausen-Hausen (DE)
- Nau, RobertD-63456 Hammersbach (DE)
- Winter, Hans-Joachim
   D-63571 Gelnhausen (DE)
- Lowenhaupt, Bernd
   D-64625 Bensheim (DE)
- (74) Representative: Stewart, Charles Geoffrey SP TYRES UK LIMITED
  Technical Division
  Fort Dunlop, Erdington,
  Birmingham B24 9QT (GB)

#### (54) Pneumatic vehicle tyre

A pneumatic vehicle tyre comprises a single ply or multi-ply radial carcass anchored to bead rings, a tread, and a breaker arrangement provided between the carcass and the tread. The breaker arrangement is preferably built up of at least two cut breaker plies with the threads or cords of the cut breaker plies, which serve as strength carriers and extend parallel to one another in the respective layer, crossing at a predeterminable angle to the central mid-circumferential plane. The tyre also comprises at least one cover ply of cords of threads extending at least substantially in the circumferential direction of the tyre and surround the breaker arrangement at least in its edge regions. To reduce the tyre weight while simultaneously ensuring good tyre characteristics the breaker arrangement (4) has threads or cords (9) of non-metallic material and a material with a low thermal shrinkage or no thermal shrinkage is used as the material for the threads or cords (8) of the cover ply (5). An extension of the tyre is ensured into the tyre mould during its manufacture through the choice of the material of the threads of cords of the cover ply (5) alone, or in conjunction with the nature of the construction and/or of the application of the cover ply (5) and/or through the nature of th construction of the threads or cords (8) of the cover ply (5), but an extension of the tyre which goes beyond this is simultaneously counteract d.





# **EUROPEAN SEARCH REPORT**

Application Number EP 95 30 5805

	Citation of document with ind	lication where expression	Dal	evant	CLASSIFICATION OF THE	
Category	of relevant pass			daim	APPLICATION (Int.CL6)	
P,X	EP-A-0 622 252 (G000 November 1994 * claims; figures *	YEAR TIRE & RUBBER) 2	1-5 11,		B60C9/22 B60C9/20	
X	EP-A-0 412 928 (G000 February 1991 * claims *	YEAR TIRE & RUBBER) 13	1-4			
<b>X</b> .	US-A-4 887 655 (IMA) December 1989 * claims; figures; e	•	1-5 17			
<b>X</b>	EP-A-0 407 071 (SUM) January 1991 * claims; figure 1;	·	1-3 17	,16,		
<b>x</b> <sup>(*)</sup>	EP-A-0 235 579 (CONTAG) 9 September 1987 * claims; figures *	TINENTAL GUMMI WERKE	1,4	,5		
X	DE-A-42 09 817 (UNI 30 September 1993 * column 2, line 38 figures * * column 1, line 10	•	1-4,10, 11,13,15		TECHNICAL FIELDS SEARCHED (Int. Cl.6) B60C	
x	EP-A-0 561 177 (CON September 1993 * claims; figures *	TINENTAL AG) 22		5,10, 13-15		
X	GB-A-2 064 445 (DUN * page 1, line 48 - figures * * page 1, line 12 - * page 2, line 21 - * page 3, line 9 -	line 18 *	1-!	5,9		
		-/				
	ocen draws up for all claims	7				
Place of search Date of completion of the search					Exemplan	
	THE HAGUE	12 February 1990	5	Bar	radat, J-L	
Y:p	CATEGORY OF CITED DOCUME articularly relevant if taken alone articularly relevant if combined with an occurent of the same category schoological background and-written disclosure	E : sarier patent d safter the filing  Other D : document cited L : document cited	T: theory or principle underlying the invention E: earlier patent document, but published on, or after the filing date D: document cited in the application L: document cited for other reasons A: member of the same patent family, corresponding			



# EUROPEAN SEARCH REPORT

Application Number EP 95 30 5805

ategory	Citation of document with in of relevant pas	Relevant to claim	CLASSIFICATION OF THE APPLICATION (Inl.Cl.6)		
<b>Χ</b>	FR-A-792 853 (MATADO * claims *	OR AG.)	1-5		
<b>x</b>	PATENT ABSTRACTS OF vol. 014 no. 379 (M- & JP-A-02 141309 (S LTD) 30 May 1990, * abstract *	·1012) ,16 August 1990	1		
4	EP-A-0 455 453 (SUM November 1991 * claims; figures;		1-19		
<b>A</b>	EP-A-0 571 204 (SP November 1993 * claims; figures *	REIFENWERKE GMBH) 24	1-5		
				TECHNICAL FIELDS SEARCHED (Int.Cl.6)	
		•			
	·				
				·	
	The present search report has i	seen drawn up for all claims	1		
	Place of search	Date of complettes of the search 12 February 199		Extension:	
<del></del> .	THE HAGUE		Baradat, J-L		
Y:p	CATEGORY OF CITED DOCUMENTS  T: theory or principle underlying the invention  E: carrier parent document, but published on, or after the filing date  particularly relevant if combined with another document of the same category  technological background  con-written disclosure  intermediate document  intermediate document  intermediate document				

		The state of the s			in and the street of the	- 17 111 - 141 11111111			ا المساعدة المساعدة المساعدة المساعدة ال
									4 p
								2	
	•								
				•	• •				
	•								
	,		4						
		•							
							,		
				y The state of the		•			
g di den	religion to the Adams of	harman grannina ay sanga	Makes of the wife spreading	para di kacampia periodi antigra periodi	en er en	ع <b>ول</b> سرويونونون هـ ارغ ا	teres and the Control of the	erosa viktori	enitation of the control
		*							THE STATE OF THE S
	Marie Marie Company	• •			•	_ + 0			
				· · · · · · · · · · · · · · · · · · ·			e e e e e e e e e e e e e e e e e e e		
	•			•					
1			*	•				•	
			•						.1.
									. •
			*						
	S. Caren					- 5.	•		
						•			
				4.4					± .
	gerial and a second					\$ \$	•		
		•							
				· · · · · · · · · · · · · · · · · · ·					
			* * * * * * * * * * * * * * * * * * *				•		
- Sp		Bertan Jayan		The state of the s	i okraje i segi	say Ash a		•	magaintagaing in a sa
	•		Angelow (	and the second s					
			• * * * * * * * * * * * * * * * * * * *	en e					•
								•	
	•		•						
			* .						
			٤		•				
					* * * * * * * * * * * * * * * * * * * *	•			
	•								